

Mobile Pipe Current Project List

Updated January 11, 2017

1. Project: Softwater Injection Line

Date: December 2016

Customer: Aera Energy

Description: 26,200 L.F of 12" pipe and pre-fabricated fittings lined with Denso® 453HT

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

2. Project: 12" Pool Line

Date: October 2016

Customer: FMOG

Description: 4200 L.F of 12" pipe and pre-fabricated spools lined with Enviroline® 405HTR

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

3. Project: Well Casing Pipe

Date: April – November 2016

Customer: Aera Energy

Description: 62,555 L.F of 5.5" and 7" well casing pipe lined with Enviroline® 2405

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

4. Project: Midway III Solar

Date: July 2016

Customer: Blattner Energy

Description: 800 pcs. of W6x8 wide flange beams with 20 mils of Sherwin Williams Fastclad ER®

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

5. Project: Marin Water Stock Pipe

Date: May 2016

Customer West Coast Pipe

Description: 38,200 L.F of pipe ranging 4" to 36" with 80 mils of YG-III

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

6. Project: EBMUD

Date: February 2016

Customer: Imperial Pipe

Description: 30,880 L. F of pipe ranging from 6" to 18" pipe with 50 mils of Synergy®

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

7. Project: Aera Energy – HOGSC Pipeline Replacement

T: 760.246.4707

E: Asterling@mobilepipe.net

W:

www.mobilepipe.net

Date: April 2015

Customer Aera Energy

Description: 8" x 15,000' of 20 mil High Temperature Epoxy Lining

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

8. Project: Lahina Waste Water Treatment Facility

Date: March 2015

Customer: County of Maui

Description: 6" to 20" DI Spools 40 mils polyurethane lining and coating

Surface Prep: SSPC-SP10 / NACE 2 Near White Metal Blast

9. Project: California Resource Corporation

Date: February 2015

Customer: Distribution NOW/ CRC

Description: 2"-6" DRL Pipe and fittings with API CML and Zinc Prime

Surface Prep: SSPC-SP10 / NACE 2 Near White Metal Blast

10. Project: Aera Energy – DWI S Grande Distribution Replacement

Date: December 2014

Customer: Aera Energy

Description: 16" x 2700', 12" x 520', 10" x 1560', 8" x 920' 20 mil of High Temperature Epoxy Lining

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

11. Project: Spokane International Airport

Date: December 2014

Customer: Ferguson Enterprises

Description: 4" through 10" pipe and 118 fittings, 8 mil Epoxy Lining for Jet Fuel Service

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

12. Project: Metropolitan Water District – Joseph Jenson Treatment Plant

Date: December 2014

Customer: West Coast Pipe

Description: 2 pcs 42" pipe spools, 80 mil Elastomeric Polyurethane lining and 8 mil exterior coating of Zinc Rich Primer and High Solids Epoxy

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

13. Project: Aera Energy – HOGS 1D Road Crossing

Date: November 2014

Customer: Aera Energy

Description: 10" x 880', 50 mil of 100% solids Flake-Filled Epoxy Coating

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

14. Project: Visalia Water Treatment Plant

Date: November 2014
Customer: Gilmore Pipe Sales
Description: 60" & 84" Pipe, 16 mil Coal Tar Epoxy Coating
Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

15. Project: API Cement for Oil Production

Date: October 2014
Customer: Occidental Petroleum
Description: 6"x 270' 8"x 500' 12"x 1,000' 16"x 6,000' & Fittings API CML
Surface Prep: SSPC – SP6/ Commercial Blast

16. Project: Powercrete HDD Drill

Date: July 2014
Customer: Sempra Energy
Description: 20" X 1900' DRL Pipe
Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

17. Project: Aera Well Casing

Date: March 2014
Customer: Aera Energy
Description: 9.5" x 7600', 20mils of High Temperature Epoxy Lining
Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

18. Project: Chevron El Segundo

Date: January 2014
Customer: Chevron
Description: 8" x 2400' 16mils of Epoxy Lining per AWWA C210
Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

19. Project: Mojave Solar

Date: January 2014
Customer: Abengoa Solar
Description: 4,200 LF' of 4" – 54" Fabricated Spools, Epoxy Urethane System for UV Exposure
Surface Prep: Abrasive Blast SSPC-7/NACE 4 Brush Off Blast

20. Project: Silver Lake Reservoir

Date: November 2013
Customer: LADWP
Description: 30"-54" Fabricated spools of Coal Tar Enamel per AWWA C203

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

21. Project: City of Calgary, Artist view Feeder main

Date: August 2013

Customer: City of Calgary

Description: 36" x 41 Fabricated Spools, 40mils Lifelast 210 Polyurethane per AWWA C222

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

22. Project: BP Cherry Point

Date: June 2013

Customer: McJunkin Redman Corp

Description: 24" x 2100', Synergy Fused Polyethylene Coated and Cement Mortar Lined

Surface Prep: - SSPC-SP6 / NACE 3 Commercial Blast Cleaning

23. Project: Wailuku Z-Force Main

Date: May 2013

Customer: Ferguson Enterprises Hawaii

Description: 40 mils of Polyurethane coating and Lining on Ductile Iron per AWWA C222

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

24. Project: Aera Energy DSD LOPS

Date: April 2013

Customer: Aera Energy

Descriptions: 16000' x 12" Sherwin Williams Macropoxy 646FC epoxy/urethane System

Surface Prep: SSPC-SP10 /NACE 2 Near-White Blast Cleaning

25. Project: SoCal Gas Directional Drill

Date: April 2013

Customer: Southern California Gas Company

Description: 8" x 32012' of Powercrete R-60 Abrasion Resistant Overlay

Surface Prep: SSPC-SP7 / NACE 4 Brush-Off Blast Cleaning

26. Project: PG&E Stock

Date: December 2012

Customer: McJunkin Redman Benicia

Description: .75 X 10000' of Hand Wrapped Cold Applied Tape

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

27. Project: Oxy THUMS Long Beach

Date: October 2012

Customer: Wilson Supply

Description: 3" X 7400' Multi Coat Paint System 2 Coats Sherwin Williams 646FC

Surface Prep: SSPC-SP10 /NACE 2 Near-White Blast Cleaning

28. Project: Lost Hills Project, Aera Energy

Date: April 2012 to June 2012

Customer: Aera Energy, Bakersfield CA

Description: 12"x 27,200', Remove Existing Lining and Re-line with Enviroline 405HT-LV Epoxy

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast

29. Project: Pearl Harbor Dry Dock #1, Pearl Harbor Naval Ship Yard

Date: April 2012

Customer: Pacific Pipe Co. Pearl City, HI

Description: 12"x 2000' Ductile Iron pipe, coated with Copoxy primer and Hi Mil Sher Tar coal tar epoxy.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

30. Project: Tule Hydroelectric Project, Southern California Edison

Date: September 2011 to November 2011

Customer: Northwest Pipe Co. Adelanto, CA

Description: 48"x 3200' pipe lined with Plasite 4500 epoxy and coated with three-coat epoxy and aliphatic urethane system.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

31. Project: Hood River Water Transmission Main, City of Hood River OR

Date: November 2011

Customer: Cal Sierra Pipe. Stockton, CA

Description: 24" pipe, coated with Life-Last Durashield 210 polyurethane and top coated with Tnemec 1075u aliphatic urethane.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

32. Project: 800 North Aqueduct Extension ,Central Utah Water Conservancy District-CWP

Date: July 2010 to October 2010

Customer: Northwest Pipe Co. Adelanto, CA

Description: 36" & 48" pipe, coated with Life-Last Durashield 210 polyurethane per AWWA C222.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

33. Project: Utah Lake – Spanish Fork to Provo Canal, Central Utah Water Conservancy District

Date: September 2010

Customer: Northwest Pipe Co. Adelanto, CA

Description: 6" to 42" pipe spools, Devoe 233H epoxy lined and Wasser moisture cure zinc and urethane coated.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

34. Project: Folsom Dam / NATOMA Relocation – Bureau of Reclamation

Date: October 2009 to January 2010

Customer: Imperial Pipe, Riverside CA

Description: 48" x 2000' pipe lined and coated with Ameron Amerlock 2 epoxy per AWWA C210.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

35. Project: Provo Reservoir Canal Pipeline / UDOT SR92 Project, Bureau of Reclamation

Date: January 2010 to March 2010

Customer: Northwest Pipe Co. Adelanto, CA

Description: 133" x 720' Lined and Coated with Life-Last Durashield 210 Polyurethane per AWWA C222.

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast

36. Project: Lindenberger Road Project – Eastern Municipal Water District

Date: September 2007

Customer: West Coast Pipe Linings, Rialto CA

Description: 37 7/8" x 9200' pipe Coated with 80 mil polyethylene tape wrapped per AWWA C214

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

37. Project: Cawelo Pipeline Replacement, Chevron USA

Date: June 2006 to October 2006

Customer: Northwest Pipe Co. Adelanto, CA

Description: 14,000' x 42", Coated with Life-Last Durashield 210 Polyurethane and Lined with Devoe Devmat 101 Epoxy.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

38. Project: Robert A. Skinner Filtration Plant, Metropolitan Water District of Southern California;

Date: May 2005 to Current

Customer: Ameron Water Transmission Group, Fontana, CA

Description: 3,000' x 147", 600' x 98"od pipe, and 1,200' x 62"od pipe, Coated with Coal Tar Enamel per AWWA C203.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

39. Project: PG&E / Trigon EPC, Line #57C natural gas pipeline, Pacific Gas and Electric

Date: February 2006 to June 2006

Customer: Marubeni Itochu Tubular America, Houston, TX



Mobile Pipe Lining and Coating
12766 Violet Road
Adelanto, CA 92301

Description: 36,000' x 24", coated with 40 mil Powercrete and Epoxy Lined with Valspar Flowliner 930HS.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning