

Mobile Pipe Current Project List

Updated December 18, 2017

- 1. Project: Salt Lake City International Airport**
Date: December 2017
Customer: ALB Piping
Description: 6000' of various size pipe for jet fuel lining per MIL-PRF-23236D Interguard® 264 Epoxy
Surface Prep: SSPC-SP5 / NACE1 White Metal Blast Cleaning
- 2. Project: Powercrete® DD Directional Drill**
Date: November 2017
Customer: Pacific Gas & Electric
Description: 6000' of 36" pipe coated with 40mils Powercrete® DD over FBE
Surface Prep: Brush of blast
- 3. Project: Shelter Island Boat Launch Facility**
Date: June 2017
Customer: R.E Staite
Description: 80 mils of Polyurethane on Wide Flange Beams for piling.
Surface Prep: SSPC-SP5 / NACE1 White Metal Blast Cleaning
- 4. Project: Camp Pendleton Raw Water Pipeline**
Date: May 2017
Customer: Imperial Pipe
Description: 36,792 L.F of 24" O.D Cement Mortar Lined Pipe with YG-III Tape System
Surface Prep: SSPC -SP10 Near White Metal Blast Cleaning
- 5. Project: Sky Harbor Airport Terminal 3 Modernization**
Date: March 2017
Customer: ALB Piping
Description: 2"-12" DRL Pipe and Fittings epoxy lined and coated Tnemec® Tneme-Liner 61
Surface Prep: SSPC- SP10 Near White Metal Blast Cleaning
- 6. Project: Soft Water Injection Line**
Date: December 2016
Customer: Aera Energy
Description: 26,200 L.F of 12" pipe and pre-fabricated fittings lined with Denso® 453HTP Epoxy
Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

7. Project: 12" Pool Line

Date: October 2016

Customer: Freeport McMoRan Oil and Gas

Description: 4200 L.F of 12" pipe and pre-fabricated spools lined with Enviroline® 405HTR Epoxy

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

8. Project: Well Casing Pipe

Date: April – November 2016

Customer: Aera Energy

Description: 62,555 L.F of 5.5" and 7" well casing pipe lined with Enviroline® 2405 Epoxy

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

9. Project: Midway III Solar

Date: July 2016

Customer: Blattner Energy

Description: 800 pcs. of W6x8 wide flange beams with 20 mils of Sherwin-Williams® Fastclad ER® Epoxy

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

10. Project: Marin Municipal Water District – Annual Contract Pipe

Date: May 2016

Customer West Coast Pipe

Description: 38,200 L.F of pipe ranging 4" to 36" with 80 mils of Polyken® YG-III Tape System

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

11. Project: East Bay Municipal Utility District

Date: February 2016

Customer: Imperial Pipe

Description: 30,880 L. F of pipe ranging from 6" to 18" pipe with 50 mils of Polyken® Synergy Fused Polyethylene

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

12. Project: Aera Energy – HOGSC Pipeline Replacement

Date: April 2015

Customer Aera Energy

Description: 8"x 15,000' of 20 mil High Temperature Epoxy Lining

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

13. Project: Lahina Waste Water Treatment Facility

Date: March 2015

Customer: County of Maui

Description: 6" to 20" DI Spools 40 mils polyurethane lining and coating

Surface Prep: SSPC-SP10 / NACE 2 Near White Metal Blast

14. Project: California Resources Corporation

Date: February 2015

Customer: Distribution NOW/ CRC

Description: 2"-6" DRL Pipe and fittings with API Cement Mortar Lining and Zinc Prime

Surface Prep: SSPC-SP10 / NACE 2 Near White Metal Blast

15. Project: Aera Energy – DWI S Grande Distribution Replacement

Date: December 2014

Customer: Aera Energy

Description: 16"x 2700', 12"x 520', 10"x 1560', 8"x 920' 20 mils of High Temperature Epoxy Lining

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

16. Project: Spokane International Airport

Date: December 2014

Customer: Ferguson Enterprises

Description: 4" through 10" pipe and 118 fittings, 8 mil Epoxy Lining for Jet Fuel Service

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

17. Project: Metropolitan Water District – Joseph Jenson Treatment Plant

Date: December 2014

Customer: West Coast Pipe

Description: 2 pcs 42" pipe spools, 80 mil Elastomeric Polyurethane lining and 8 mil exterior coating of Zinc Rich Primer and High Solids Epoxy

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast Cleaning

18. Project: Aera Energy – HOGS 1D Road Crossing

Date: November 2014

Customer: Aera Energy

Description: 10"x 880', 50 mil of 100% solids Flake-Filled Epoxy Coating

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

19. Project: Visalia Water Treatment Plant

Date: November 2014

Customer: Gilmore Pipe Sales

Description: 60" & 84" Pipe, 16 mil Coal Tar Epoxy Coating

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

20. Project: API Cement for Oil Production

Date: October 2014

Customer: Occidental Petroleum

Description: 6"x 270' 8"x 500' 12"x 1,000' 16"x 6,000' & Fittings API Cement Mortar Lining

Surface Prep: SSPC – SP6/ Commercial Blast

21. Project: Powercrete HDD Drill

Date: July 2014

Customer: Sempra Energy

Description: 20" X 1900' DRL Pipe Powercrete® Epoxy

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

22. Project: Aera Well Casing

Date: March 2014

Customer: Aera Energy

Description: 9.5" x 7600', 20mils of High Temperature Epoxy Lining

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

23. Project: Chevron El Segundo

Date: January 2014

Customer: Chevron

Description: 8" x 2400' 16mils of Epoxy Lining per AWWA C210

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

24. Project: Mojave Solar

Date: January 2014

Customer: Abengoa Solar

Description: 4,200 LF' of 4" – 54" Fabricated Spools, Epoxy Urethane System for UV Exposure

Surface Prep: Abrasive Blast SSPC-7/NACE 4 Brush Off Blast

25. Project: Silver Lake Reservoir

Date: November 2013

Customer: LADWP

Description: 30"-54" Fabricated spools of Coal Tar Enamel per AWWA C203

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

26. Project: City of Calgary, Artist view Feeder main

Date: August 2013

Customer: City of Calgary

Description: 36" x 41 Fabricated Spools, 40mils Lifelast™ 210 Polyurethane per AWWA C222

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

27. Project: BP Cherry Point

Date: June 2013

Customer: McJunkin Redman Corp

Description: 24" x 2100', Polyken® Synergy Fused Polyethylene Coated and Cement Mortar Lined

Surface Prep: - SSPC-SP6 / NACE 3 Commercial Blast Cleaning

28. Project: Wailuku Z-Force Main

Date: May 2013

Customer: Ferguson Enterprises Hawaii

Description: 40 mils of Polyurethane coating and Lining on Ductile Iron per AWWA C222

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

29. Project: Aera Energy DSD LOPS

Date: April 2013

Customer: Aera Energy

Descriptions: 16000' x 12" Sherwin-Williams Macropoxy® 646FC epoxy/urethane System

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

30. Project: SoCal Gas Directional Drill

Date: April 2013

Customer: Southern California Gas Company

Description: 8" x 32012' of Powercrete® R-60 Abrasion Resistant Overlay

Surface Prep: SSPC-SP7 / NACE 4 Brush-Off Blast Cleaning

31. Project: PG&E Stock Pipe

Date: December 2012

Customer: McJunkin Redman Benicia

Description: .75 X 10000' of Polyken® Cold Applied Tape

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

32. Project: Oxy THUMS Long Beach

Date: October 2012

Customer: Wilson Supply

Description: 3" X 7400' Multi Coat Paint System 2 Coats Sherwin-Williams® Macropoxy® 646FC

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

33. Project: Lost Hills Project, Aera Energy

Date: April 2012 to June 2012

Customer: Aera Energy, Bakersfield CA

Description: 12"x 27,200', Remove Existing Lining and Re-line with Enviroline® 405HT-LV Epoxy

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast

34. Project: Pearl Harbor Dry Dock #1, Pearl Harbor Naval Ship Yard

Date: April 2012

Customer: Pacific Pipe Co. Pearl City, HI

Description: 12"x 2000' Ductile Iron pipe, coated with Shwerwin-Williams® Copoxy primer and Hi-Mil Sher-Tar™ coal tar epoxy.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

35. Project: Tule Hydroelectric Project, Southern California Edison

Date: September 2011 to November 2011

Customer: Northwest Pipe Co. Adelanto, CA

Description: 48"x 3200' pipe lined with Plasite® 4500 epoxy and coated with three-coat epoxy and aliphatic urethane system.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

36. Project: Hood River Water Transmission Main, City of Hood River OR

Date: November 2011

Customer: Cal Sierra Pipe. Stockton, CA

Description: 24" pipe, coated with LifeLast® Durashield™ 210 polyurethane and top coated with Tnemec® 1075u aliphatic urethane.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

37. Project: 800 North Aqueduct Extension, Central Utah Water Conservancy District-CWP

Date: July 2010 to October 2010

Customer: Northwest Pipe Co. Adelanto, CA

Description: 36" & 48" pipe, coated with LifeLast® Durashield™ 210 polyurethane per AWWA C222.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

38. Project: Utah Lake – Spanish Fork to Provo Canal, Central Utah Water Conservancy District

Date: September 2010

Customer: Northwest Pipe Co. Adelanto, CA

Description: 6" to 42" pipe spools, Devoe® 233H epoxy lined and Wasser® moisture cure zinc and urethane coated.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

39. Project: Folsom Dam / NATOMA Relocation – Bureau of Reclamation

Date: October 2009 to January 2010

Customer: Imperial Pipe, Riverside CA

Description: 48" x 2000' pipe lined and coated with Ameron® Amerlock 2 epoxy per AWWA C210.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

40. Project: Provo Reservoir Canal Pipeline / UDOT SR92 Project, Bureau of Reclamation

Date: January 2010 to March 2010

Customer: Northwest Pipe Co. Adelanto, CA

Description: 133" x 720' Lined and Coated with LifeLast® Durashield™ 210 Polyurethane per AWWA C222.

Surface Prep: SSPC-SP5 / NACE 1 White Metal Blast

41. Project: Lindenberger Road Project – Eastern Municipal Water District

Date: September 2007

Customer: West Coast Pipe Linings, Rialto CA

Description: 37 7/8" x 9200' pipe Coated with 80 mil polyethylene tape wrapped per AWWA C214

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

42. Project: Cawelo Pipeline Replacement, Chevron USA

Date: June 2006 to October 2006

Customer: Northwest Pipe Co. Adelanto, CA

Description: 14,000' x 42", Coated with LifeLast® Durashield™ 210 Polyurethane and Lined with Devoe® Devmat™ 101 Epoxy.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning



Mobile Pipe Lining and Coating
12766 Violet Road
Adelanto, CA 92301

43. Project: Robert A. Skinner Filtration Plant, Metropolitan Water District of Southern California;

Date: May 2005 to Current

Customer: Ameron Water Transmission Group, Fontana, CA

Description: 3,000' x 147", 600' x 98" O.D pipe, and 1,200' x 62" O.D pipe, Coated with Coal Tar Enamel per AWWA C203

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning

44. Project: PG&E / Trigon EPC, Line #57C natural gas pipeline, Pacific Gas and Electric

Date: February 2006 to June 2006

Customer: Marubeni Itochu Tubular America, Houston, TX

Description: 36,000' x 24", coated with 40 mil Powercrete® and Epoxy Lined with Valspar® Flowliner 930HS.

Surface Prep: SSPC-SP10 / NACE 2 Near-White Blast Cleaning